

Project 2: Ants Vs. SomeBees

ants.zip (ants.zip)



Add WeChat powcoder

The bees are coming!

Create a better soldier

With inherit-ants.

Introduction

Grading Updates

Parts 1, 2 and 3, are the only required parts. Submitting Parts 1, 2, and 3 will be worth 60 points.

There will be no EC early submission points. There will be no composition grading, nor checkpoint, but a submission by the deadline will earn you 4 pts for the checkpoint, and 2 points for composition. (6 points total). You must complete phase 1 and phase to get the 8 points.

Phases 1, 2, and 3 will be scaled to 54 points. Phase 4 will be EC for everyone, up to 73 points total. (Basically, `ants_score = min(73, raw_score*(54/41))`.)

Important submission note: For full credit,

- Submit with Phase 1 and 2 complete by **Sunday, November 20** (worth 4 pts).
- Submit with all phases complete by **Thursday, December 1**. You can get 2 EC points by submitting the entire project by **Tuesday, November 29**.

Try to attempt the problems in order, as some later problems will depend on earlier problems in their implementation and therefore also when running `ok` tests.

The entire project can be completed with a partner. Consider using Visual Studio Code Live Share (<https://code.visualstudio.com/learn/collaboration/live-share>) to synchronously work on code with your partner. <<<<< HEAD

===== >

~~You can get 2 EC points by submitting the entire project by~~ ~~~**Tuesday, November 29**.~~

The entire project is now due **Monday, December 5**. See Grading Updates below for more details. >>>> afeaafbad4293a0954930a672c655275ec7feadd1

In this project, you will create a tower defense

(https://secure.wikimedia.org/wikipedia/en/wiki/Tower_defense) game called Ants Vs. SomeBees. As the ant queen, you populate your colony with the bravest ants you can muster. Your ants must protect their queen from the evil bees that invade your territory. Irritate the bees enough by throwing leaves at them, and they will be vanquished. Fail to irritate the irksome intruders adequately and your queen will succumb to the bees' wrath. This game is inspired by PopCap Games' Plants Vs. Zombies (<https://www.ea.com/studios/popcap/plants-vs-zombies>).

This project uses an object-oriented programming paradigm, focusing on material from Chapter 2.5 (<http://composingprograms.com/pages/25-object-oriented-programming.html>). Composing Programs. The project also involves understanding, extending, and testing a large program.

Assignment Project Exam Help

Download starter files Add WeChat powcoder

The `ants.zip` (`ants.zip`) archive contains several files, but all of your changes will be made to `ants.py`.

- `ants.py` : The game logic of Ants Vs. SomeBees
- `ants_gui.py` : The original GUI for Ants Vs. SomeBees
- `gui.py` : A new GUI for Ants Vs. SomeBees.
- `graphics.py` : Utilities for displaying simple two-dimensional animations
- `utils.py` : Some functions to facilitate the game interface
- `ucb.py` : Utility functions for CS 88
- `state.py` : Abstraction for gamestate for `gui.py`
- `assets` : A directory of images and files used by `gui.py`
- `img` : A directory of images used by `ants_gui.py`
- `ok` : The autograder
- `proj3.ok` : The `ok` configuration file
- `tests` : A directory of tests used by `ok`

You can obtain all the files needed for this project by downloading this zip archive (`ants.zip`).

Logistics

This is a project. You may work with one other partner. You should not share your code with students who are not your partner or copy from anyone else's solutions.

In the end, you will submit one project for both partners. The project is worth 60 points.

The project is worth 60 points. 54 points are assigned for correctness, 2 points for composition, 4 points for submitting Phase 1 and 2 by the checkpoint date

~~Additionally, there are some extra credit point opportunities.~~ ~~~You can get 2 EC point for submitting the entire project by~~ ~~~**Tuesday, November 29**, and~~ ~~~2 EC points for submitting the extra credit problem.~~

~~**Important:**~~ ~~~In order to receive all of the extra credit points for Ants,~~ ~~~your implementation of the entire project,~~ ~~~including the EC problem,~~ ~~~must be submitted by the early submission deadline.~~

Grading Updates

Parts 1, 2 and 3, are the only required parts. Submitting Parts 1, 2, and 3 will be worth 60 points. There will be no EC early submission points. There will be no composition grading, nor checkpoint, but a submission by the deadline (**Monday, December 5**) will earn you 4 pts for the checkpoint, and 2 points for composition. (6 points total). You must complete phase 1 and phase to get the 8 points. Phases 1, 2, and 3 will be scaled to 54 points. Phase 4 will be EC for everyone, up to 70 points total. (Basically, $\text{ants_score} = \min(70, \text{raw_score} * (54/41))$).

You will turn in the following files:

- `ants.py`

Assignment Project Exam Help

You do not need to modify or turn in any other files to complete the project. To submit the project, run the following command:

`https://powcoder.com`

`python3 ok --submit`

Add WeChat powcoder

You will be able to view your submissions on the Ok dashboard (<https://bpy.org/>).

For the functions that we ask you to complete, there may be some initial code that we provide. If you would rather not use that code, feel free to delete it and start from scratch. You may also add new function definitions as you see fit.

However, please do **not** modify any other functions. Doing so may result in your code failing our autograder tests. Also, please do not change any function signatures (names, argument order, or number of arguments).

Testing

Throughout this project, you should be testing the correctness of your code. It is good practice to test often, so that it is easy to isolate any problems.

We have provided an **autograder** called `ok` to help you with testing your code and tracking your progress.

The primary purpose of `ok` is to test your implementations, but there is a catch. At first, the test cases are *locked*. To unlock tests, run the following command from your terminal.

`python3 ok -u`

Run the specific version of this command as detailed in each problem. This command will start an interactive prompt that looks like:

```
=====
Assignment: Ants Vs. SomeBees
OK, version ...
=====

~~~~~
Unlocking tests

At each "? ", type what you would expect the output to be.
Type exit() to quit

-----
Question 0 > Suite 1 > Case 1
(cases remaining: 1)

>>> Code here
?
```

At the ?, you can type what you expect the output to be. If you are correct, then this test case will be available the next time you run the autograder.

The idea is to understand *conceptually* what your program should do first, before you start writing any code.

Assignment Project Exam Help

Once you have unlocked some tests and written some code, you can check the correctness of your program using the tests that you have unlocked:

python3 ok

<https://powcoder.com>

Most of the time, you will want to focus on a particular question. Use the -q option as directed in the problems below.


Add WeChat powcoder

The tests folder is used to store autograder tests, so make sure **not to modify it**. You may lose all your unlocking progress if you do. If you need to get a fresh copy, you can download the zip archive (ants.zip) and copy it over, but you will need to start unlocking from scratch.

If you are ever stuck on a problem, you should add print statements to your code to help debug. Use `print("DEBUG:", variable)` to see the value of variable and still have your tests pass.

The Game

A game of Ants Vs. SomeBees consists of a series of turns. In each turn, new bees may enter the ant colony. Then, new ants are placed to defend their colony. Finally, all insects (ants, then bees) take individual actions. Bees either try to move toward the end of the tunnel or sting ants in their way. Ants perform a different action depending on their type, such as collecting more food or throwing leaves at the bees. The game ends either when a bee reaches the end of the tunnel (you lose), the bees destroy the QueenAnt if it exists (you lose), or the entire bee fleet has been vanquished (you win).



Core concepts

The Colony. This is where the game takes place. The colony consists of several Places that are chained together to form a tunnel where bees can travel through. The colony also has some quantity of food which can be expended in order to place an ant in a tunnel.

Places. A place links to another place to form a tunnel. The player can put a single ant into each place. However, there can be many bees in a single place.

Assignment Project Exam Help
<https://powcoder.com>

The Hive. This is the place where bees originate. Bees exit the beehive to enter the ant colony.

Ants. Players place an ant into the colony by selecting from the available ant types at the top of the screen. Each type of ant takes a different action and requires a different amount of colony food to place. The two most basic ant types are the `HarvesterAnt`, which adds one food to the colony during each turn, and the `ThrowerAnt`, which throws a leaf at a bee each turn. You will be implementing many more!

Bees. In this game, bees are the antagonistic forces that the player must defend the ant colony from. Each turn, a bee either advances to the next place in the tunnel if no ant is in its way, or it stings the ant in its way. Bees win when at least one bee reaches the end of a tunnel.

Core classes

The concepts described above each have a corresponding class that encapsulates the logic for that concept. Here is a summary of the main classes involved in this game:


- **GameState** : Represents the colony and some state information about the game, including how much food is available, how much time has elapsed, where the `AntHomeBase` is, and all the `Place`s in the game.
- **Place** : Represents a single place that holds insects. At most one `Ant` can be in a single place, but there can be many `Bee`s in a single place. `Place` objects have an `exit` to the left and an `entrance` to the right, which are also places. Bees travel through a tunnel by moving to a `Place`'s `exit`.
- **Hive** : Represents the place where `Bee`s start out (on the right of the tunnel).
- **AntHomeBase** : Represents the place `Ant`s are defending (on the left of the tunnel). If Bees get here, they win :(
- **Insect** : A superclass for `Ant` and `Bee`. All insects have `health` attribute, representing their

remaining health, and a `place` attribute, representing the `Place` where they are currently located. Each turn, every active `Insect` in the game performs its `action`.

- **Ant** : Represents ants. Each Ant subclass has special attributes or a special action that distinguish it from other Ant types. For example, a `HarvesterAnt` gets food for the colony and a `ThrowerAnt` attacks Bees. Each ant type also has a `food_cost` attribute that indicates how much it costs to deploy one unit of that type of ant.
- **Bee** : Represents bees. Each turn, a bee either moves to the `exit` of its current `Place` if the `Place` is not blocked by an ant, or stings the ant occupying its same `Place`.

Game Layout

Below is a visualization of a `GameState`. As you work through the unlocking tests and problems, we recommend drawing out similar diagrams to help your understanding.




Assignment Project Exam Help

Object map

To help visualize how all the classes fit together, we've also created an object map for you to reference as you work, which you can find here ([assets/ants_diagram.pdf](#)):

Add WeChat powcoder



Playing the game

The game can be run in two modes: as a text-based game or using a graphical user interface (GUI). The game logic is the same in either case, but the GUI enforces a turn time limit that makes playing the game more exciting. The text-based interface is provided for debugging and development.

The files are separated according to these two modes. `ants.py` knows nothing of graphics or turn time limits.

To start a text-based game, run

```
python3 ants_text.py
```

To start a graphical game, run

```
python3 gui.py
```

When you start the graphical version, a new browser window should appear. In the starter implementation, you have unlimited food and your ants can only throw leaves at bees in their current Place. Before you complete Problem 2, the GUI may crash since it doesn't have a full conception of what a Place is yet! Try playing the game anyway! You'll need to place a lot of ThrowerAnts (the second type) in order to keep the bees from reaching your queen.

The game has several options that you will use throughout the project, which you can view with `python3 ants_text.py --help`.

```
usage: ants_text.py [-h] [-d DIFFICULTY] [-w] [-f food FOOD]
```

Play Ants vs. SomeBees

optional arguments:

- h, --help show this help message and exit
- d DIFFICULTY sets difficulty of game (test/easy/normal/hard/extrahard)
- w, --water loads a full layout with water
- food FOOD number of food to start with when testing

Assignment Project Exam Help

Add WeChat powcoder

Getting Started Videos

These videos may provide some helpful direction for tackling the coding problems on the project. Note that these videos start providing help at Q4 and that the Q12 video does not apply to this version of the project. You can watch the videos provided here (<https://www.youtube.com/watch?v=QrWrKAuxSy8&list=PLx38hZJ5RLZdWOZuRdQp7pcbswC4DT3pA&index=1>).

To see these videos, you should be logged into your berkeley.edu email.

Phase 1: Basic gameplay

Important submission note: For full credit, submit with Phase 1 and 2 complete by **Thursday, November 17** (worth 4 pts).

In the first phase you will complete the implementation that will allow for basic gameplay with the two basic Ants: the HarvesterAnt and the ThrowerAnt.

Problem 0 (0 pt)

Answer the following questions with your partner after you have read the *entire ants.py* file.

To submit your answers, run:

```
python3 ok -q 00 -u
```

If you get stuck while answering these questions, you can try reading through *ants.py* again, consult the core concepts/classes sections above, or ask a question in the Question 0 thread on Piazza.

1. What is the significance of an Insect's health attribute? Does this value change? If so, how?
2. Which of the following is a class attribute of the Insect class?
3. Is the health attribute of the Ant class an instance attribute or a class attribute? Why?
4. Is the damage attribute of an Ant subclass (such as ThrowerAnt) an instance attribute or class attribute? Why?
5. Which class do both Ant and Bee inherit from?
6. What do instances of Ant and instances of Bee have in common?
7. How many insects can be in a single Place at any given time (before Problem 8)?
8. What does a Bee do during one of its turns?
9. When is the game lost?

Remember to run:

Assignment Project Exam Help

```
python3 ok -q 00 -u
```

Problem 1 (3 pt)

<https://powcoder.com>


Before writing any code, read the instructions and test your understanding of the problem:

```
python3 ok -q 01 -u
```

Add WeChat powcoder

Part A: Currently, there is no cost for placing any type of Ant, and so there is no challenge to the game. The base class Ant has a food_cost of zero. Override this class attribute for HarvesterAnt and ThrowerAnt according to the "Food Cost" column in the table below.

Class	Food Cost	Initial Health
 HarvesterAnt	2	1



Part B: Now that placing an `Ant` costs food, we need to be able to gather more food! To fix this issue, implement the `HarvesterAnt` class. A `HarvesterAnt` is a type of `Ant` that adds one food to the `gamestate.food` total as its `action`.

After writing code, test your implementation:

```
python3 ok -q 01
```

Assignment Project Exam Help

Try playing the game by running `python3 gui.py`. Once you have placed a `HarvesterAnt`, you should accumulate food each turn. You can also place `ThrowerAnt`s, but you'll see that they can only attack bees that are in their `Place`, making it a little difficult to win.

<https://powcoder.com>

Problem 2 (3 pt)

Before writing any code, read the instructions and test your understanding of the problem:

```
python3 ok -q 02 -u
```

Add WeChat powcoder

In this problem, you'll complete `Place.__init__` by adding code that tracks entrances. Right now, a `Place` keeps track only of its `exit`. We would like a `Place` to keep track of its entrance as well. A `Place` needs to track only one `entrance`. Tracking entrances will be useful when an `Ant` needs to see what `Bee`s are in front of it in the tunnel.


However, simply passing an entrance to a `Place` constructor will be problematic; we would need to have both the `exit` and the `entrance` before creating a `Place`! (It's a chicken or the egg (https://en.wikipedia.org/wiki/Chicken_or_the_egg) problem.) To get around this problem, we will keep track of entrances in the following way instead. `Place.__init__` should use this logic:

- A newly created `Place` always starts with its `entrance` as `None`.
- If the `Place` has an `exit`, then the `exit`'s `entrance` is set to that `Place`.

Hint: Remember that when the `__init__` method is called, the first parameter, `self`, is bound to the newly created object

Hint: Try drawing out two `Place`s next to each other if things get confusing. In the GUI, a place's `entrance` is to its right while the `exit` is to its left.

Hint: Remember that `Places` are not stored in a list, so you can't index into anything to access them. This means that you **can't** do something like `colony[index + 1]` to access an adjacent `Place`. How can you move from one place to another?



Example: `AntColony` with dimensions (1, 9)

After writing code, test your implementation:

```
python3 ok -q 02
```

Problem 3 (3 pt)

Before writing any code, read the instructions and test your understanding of the problem.

```
python3 ok -q 03 -u
```

<https://powcoder.com>

In order for a `ThrowerAnt` to throw a leaf, it must know which bee to hit. The provided implementation of the `nearest_bee` method in the `ThrowerAnt` class only allows them to hit bees in the same `Place`. Your job is to fix it so that a `ThrowerAnt` will throw a leaf at the nearest bee in front of it that is **not still in the Hive**. This includes bees that are in the same `Place` as a `ThrowerAnt`.

Hint: All `Places` have an `is_hive` attribute which is `True` when that place is the `Hive`.

Change `nearest_bee` so that it returns a random `Bee` from the nearest place that contains bees. Your implementation should follow this logic:

- Start from the current `Place` of the `ThrowerAnt`.
- For each place, return a random bee if there is any, and if not, inspect the place in front of it (stored as the current place's `entrance`).
- If there is no bee to attack, return `None`.

Hint: The `random_bee` function provided in `ants.py` returns a random bee from a list of bees or `None` if the list is empty.

Hint: As a reminder, if there are no bees present at a `Place`, then the `bees` attribute of that `Place` instance will be an empty list.

Hint: Having trouble visualizing the test cases? Try drawing them out on paper! The sample diagram provided in Game Layout shows the first test case for this problem.

After writing code, test your implementation:

```
python3 ok -q 03
```

After implementing `nearest_bee`, a `ThrowerAnt` should be able to `throw_at` a `Bee` in front of it that is not still in the `Hive`. Make sure that your ants do the right thing! To start a game with ten food (for easy testing):

```
python3 gui.py --food 10
```

Phase 2: Ants!

Important submission note: For full credit,

- Submit with Phase 1 and 2 complete by **Thursday, November 17** (worth 4 pts).

Now that you've implemented basic gameplay with two types of `Ant`s, let's add some flavor to the ways ants can attack bees. In this phase, you'll be implementing several different `Ant`s with different attack strategies.

After you implement each `Ant` subclass in this section, you'll need to set its `implemented` class attribute to `True` so that that type of ant will show up in the GUI. Feel free to try out the game with each new ant to test the functionality!

With your Phase 2 ants, try `python3 gui.py -d easy` to play against a full swarm of bees in a multi-tunnel layout and try `-d normal`, `-d hard`, or `-d extra-hard` if you want a real challenge. If the bees are too numerous to vanquish, you might need to create some new ants.

Problem 4 (5 pt)

Add WeChat powcoder

Before writing any code, read the instructions and test your understanding of the problem:


```
python3 ok -q 04 -u
```

A `ThrowerAnt` is a powerful threat to the bees, but it has a high food cost. In this problem, you'll implement two subclasses of `ThrowerAnt` that are less costly but have constraints on the distance they can throw:

- The `LongThrower` can only `throw_at` a `Bee` that is found after following at least 5 entrance transitions. It cannot hit `Bee`s that are in the same `Place` as it or the first 4 `Place`s in front of it. If there are two `Bee`s, one too close to the `LongThrower` and the other within its range, the `LongThrower` should only throw at the farther `Bee`, which is within its range, instead of trying to hit the closer `Bee`.
- The `ShortThrower` can only `throw_at` a `Bee` that is found after following at most 3 entrance transitions. It cannot throw at any bees further than 3 `Place`s in front of it.

Neither of these specialized throwers can `throw_at` a `Bee` that is exactly 4 `Place`s away.

Class	Food Cost	Initial Health



Assignment Project Exam Help

<https://powcoder.com>

To implement these new throwing ants, your `ShortThrower` and `LongThrower` classes should inherit the `nearest_bee` method from the base `ThrowerAnt` class. The logic of choosing which bee a thrower ant will attack is the same, except the `ShortThrower` and `LongThrower` ants have a maximum and minimum range, respectively.

To do this, modify the `nearest_bee` method to reference `min_range` and `max_range` attributes, and only return a bee if it is within range.

Make sure to give these `min_range` and `max_range` attributes appropriate values in the `ThrowerAnt` class so that the behavior of `ThrowerAnt` is unchanged. Then, implement the subclasses `LongThrower` and `ShortThrower` with appropriately constrained ranges.

You should **not** need to repeat any code between `ThrowerAnt`, `ShortThrower`, and `LongThrower`.

Hint: `float('inf')` returns an infinite positive value represented as a float that can be compared with other numbers.

Hint: You can chain inequalities in Python: e.g. `2 < x < 6` will check if `x` is between 2 and 6. Also, `min_range` and `max_range` should mark an inclusive range.

Important: Make sure your class attributes are called `max_range` and `min_range`. The tests directly reference these attribute names, and will error if you use another name for these attributes.

Don't forget to set the `implemented` class attribute of `LongThrower` and `ShortThrower` to `True`.

After writing code, test your implementation (rerun the tests for q 03 to make sure they still work):

```
python3 ok -q 03
python3 ok -q 04
```

Problem 5 (7 pt)

Before writing any code, read the instructions and test your understanding of the problem:

```
python3 ok -q 05 -u
```

Implement the `FireAnt`, which does damage when it receives damage. Specifically, if it is damaged by `amount` health units, it does a damage of `amount` to all bees in its place (this is called *reflected damage*). If it dies, it does an additional amount of damage, as specified by its `damage` attribute, which has a default value of 3 as defined in the `FireAnt` class.

To implement this, override `FireAnt`'s `reduce_health` method. Your overridden method should call the `reduce_health` method inherited from the superclass (`Ant`) to reduce the current `FireAnt` instance's health. Calling the *inherited* `reduce_health` method on a `FireAnt` instance reduces the insect's health by the given `amount` and removes the insect from its place if its `health` reaches zero or lower.

Assignment Project Exam Help

Hint: Do not call `self.reduce_health`, or you'll end up stuck in a recursive loop. (Can you see why?)

<https://powcoder.com>

However, your method needs to also include the reflective damage logic:

- Determine the reflective damage amount: start with the `amount` inflicted on the ant, and then add `damage` if the ant's health has dropped to 0.
- For each bee in the place, damage them with the total amount by calling the appropriate `reduce_health` method for each bee.

Important: The `FireAnt` must do its damage *before* being removed from its `place`, so pay careful attention to the order of your logic in `reduce_health`.

Class	Food Cost	Initial Health
 FireAnt	5	3

Hint: Damaging a bee may cause it to be removed from its place. If you iterate over a list, but change the contents of that list at the same time, you may not visit all the elements (<https://docs.python.org/3/tutorial/controlflow.html#for-statements>). This can be prevented by making a copy of the list. You can either use a list slice, or use the built-in `list` function.

```
>>> lst = [1,2,3,4]
>>> lst[::]
[1, 2, 3, 4]
>>> list(lst)
[1, 2, 3, 4]
>>> lst[::] is not lst and list(lst) is not lst
True
```

Once you've finished implementing the `FireAnt`, give it a class attribute `implemented` with the value `True`.

Note: Even though you are overriding the superclass's `reduce_health` function (`Ant.reduce_health`), you can still use this method in your implementation by calling it. Note this is not recursion. (Why not?)

Assignment Project Exam Help

```
python3 ok -q 05
```

<https://powcoder.com>

You can also test your program by playing a game or two! A `FireAnt` should destroy all co-located Bees when it is stung. To start a game with ten food (for easy testing):

```
python3 gui.py --food 10
```

Add WeChat powcoder

Make sure to submit by the checkpoint deadline **Thursday, November 17** using the following command:

```
python3 ok --submit
```

You can check to ensure that you have completed all Phase 1 and Phase 2 problems by running:

```
python3 ok --score
```

Congratulations! You have finished Phase 1 and Phase 2 of this project!

Phase 3: More Ants!

Important submission note: For full credit,

- Submit with Phase 1 and 2 complete by **Thursday, November 17** (worth 4 pts).
- Submit with all phases complete by **Thursday, December 1**.

Problem 6 (3 pt)

Before writing any code, read the instructions and test your understanding of the problem:

```
python3 ok -q 06 -u
```

We are going to add some protection to our glorious home base by implementing the `WallAnt`, an ant that does nothing each turn. A `WallAnt` is useful because it has a large health value.

Class	Food Cost	Initial Health
 WallAnt	4	4

Assignment Project Exam Help

Unlike with previous ants, we have not provided you with a class header. Implement the `WallAnt` class from scratch. Give it a class attribute `name` with the value 'Wall' (so that the graphics work) and a class attribute `implemented` with the value `True` (so that you can use it in a game).

<https://powcoder.com>

Hint: To start, take a look at how the previous problems' ants were implemented!

After writing code, test your implementation:

Add WeChat powcoder

```
python3 ok -q 06
```

Problem 7 (7 pt)

Implement the `HungryAnt`, which will select a random Bee from its place and eat it whole. After eating a Bee, a `HungryAnt` must spend 3 turns chewing before eating again. If there is no bee available to eat, `HungryAnt` will do nothing.

Before writing any code, read the instructions and test your understanding of the problem:

```
python3 ok -q 07 -u
```

We have not provided you with a class header. Implement the `HungryAnt` class from scratch. Give it a class attribute `name` with the value 'Hungry' (so that the graphics work) and a class attribute `implemented` with the value `True` (so that you can use it in a game).

Hint: When a Bee is eaten, it should lose all its health. Is there an existing function we can call on a Bee that can reduce its health to 0?



Class	Food Cost	Initial Health
HungryAnt 	4	1

Give HungryAnt a `chew_duration` **class** attribute that stores the number of turns that it will take a HungryAnt to chew (set to 3). Also, give each HungryAnt an **instance** attribute `chew_countdown` that counts the number of turns it has left to chew (initialized to 0, since it hasn't eaten anything at the beginning. You can also think of `chew_countdown` as the number of turns until a HungryAnt can eat another Bee).

Implement the `action` method of the HungryAnt : First, check if it is chewing; if so, decrement its `chew_countdown` by 1. Otherwise, eat a random Bee in its place by reducing the Bee 's health to 0. Make sure to set the `chew_countdown` when a Bee is eaten!

Hint: Other than the `action` method, make sure you implement the `__init__` method too so the HungryAnt starts off with the appropriate amount of health !

After writing code, test your implementation:

```
python3 ok -q 07
```

Assignment Project Exam Help

We now have some great offensive troops to help vanquish the bees, but let's make sure we're also keeping our defensive efforts up. In this phase, you will implement ants that have special defensive capabilities such as increased health and the ability to protect other ants.


Problem 8 (7 pt)

Add WeChat powcoder

Before writing any code, read the instructions and test your understanding of the problem:

```
python3 ok -q 08 -u
```

Right now, our ants are quite frail. We'd like to provide a way to help them last longer against the onslaught of the bees. Enter the `BodyguardAnt` .

Class	Food Cost	Initial Health
	4	2

BodyguardAnt		
--------------	--	--

A `BodyguardAnt` differs from a normal ant because it is a `ContainerAnt`; it can contain another ant and protect it, all in one `Place`. When a `Bee` stings the ant in a `Place` where one ant contains another, only the container is damaged. The ant inside the container can still perform its original action. If the container perishes, the contained ant still remains in the place (and can then be damaged).

Each `ContainerAnt` has an instance attribute `ant_contained` that stores the ant it contains. This ant, `ant_contained`, initially starts off as `None` to indicate that there is no ant being stored yet. Implement the `store_ant` method so that it sets the `ContainerAnt`'s `ant_contained` instance attribute to the passed in `ant` argument. Also implement the `ContainerAnt`'s `action` method to perform its `ant_contained`'s action if it is currently containing an ant.

In addition, you will need to make the following modifications throughout your program so that a container and its contained ant can both occupy a place at the same time (a maximum of two ants per place), but only if exactly one is a container:

1. There is an `Ant.can_contain` method, but it always returns `False`. Override the method `ContainerAnt.can_contain` so that it takes an ant `other` as an argument and returns `True` if:
 - o This `ContainerAnt` does not already contain another ant.
 - o The other ant is not a container.
2. Modify `Ant.add_to` to allow a container and a non-container ant to occupy the same place according to the following rules:
 - o If the ant originally occupying a place can contain the ant being added, then both ants occupy the place and the original ant contains the ant being added.
 - o If the ant being added can contain the ant originally in the space, then both ants occupy the place and the (container) ant being added contains the original ant.
 - o If neither `Ant` can contain the other, raise the same `AssertionError` as before (the one already present in the starter code).
 - o **Important:** If there are two ants in a specific `Place`, the `ant` attribute of the `Place` instance should refer to the container ant, and the container ant should contain the non-container ant.
3. Add a `BodyguardAnt.__init__` that sets the initial amount of health for the ant.

Hint: You may find the `is_container` attribute that each `Ant` has useful for checking if a specific `Ant` is a container. You should also take advantage of the `can_contain` method you wrote and avoid repeating code.

The constructor of `ContainerAnt.__init__` is implemented as follows:

```
def __init__(self, *args, **kwargs):
    super().__init__(*args, **kwargs)
    self.ant_contained = None
```

`args` is bound to all positional arguments (which are all arguments passed without keywords), and `kwargs` is bound to all the keyword arguments. This ensures that both sets of arguments are passed to the `Ant` constructor.

Effectively, this means the constructor is exactly the same as its parent class's constructor (`Ant.__init__`) but here we also set `self.ant_contained = None`.

Note: Here we will expand on the syntax used above if you are interested. We would like to write a function that accepts an arbitrary number of arguments, and then calls another function using exactly those arguments. Here's how it works.

Instead of listing formal parameters for a function, you can write `args`, which represents all of the arguments that get passed into the function. We can then call another function with these same arguments by passing these args into this other function. For example:

```
def printed(f):
...     def print_and_return(*args):
...         result = f(*args)
...         print('Result:', result)
...         return result
...     return print_and_return
>>> printed_pow = printed(pow)
>>> printed_pow(2, 8)
Result: 256
256
>>> printed_abs = printed(abs)
>>> printed_abs(-10)
Result: 10
10
```

Here, we can pass any number of arguments into `print_and_return` via the `*args` syntax. We can also use `*args` inside our `print_and_return` function to make another function call with the same arguments.

Once you've finished implementing the `BodyguardAnt`, give it a `canAttack` attribute implemented with the value `True`.

After writing code, test your implementation:

`python3 ok -q 08`

Add WeChat powcoder


Problem 9 (3 pt)

Before writing any code, read the instructions and test your understanding of the problem:

`python3 ok -q 09 -u`

The `BodyguardAnt` provides great defense, but they say the best defense is a good offense. The `TankAnt` is a container ant that protects an ant in its place and also deals 1 damage to all bees in its place each turn.

Class	Food Cost	Initial Health



We have not provided you with a class header. Implement the `TankAnt` class from scratch. Give it a class attribute `name` with the value 'Tank' (so that the graphics work) and a class attribute `implemented` with the value `True` (so that you can use it in a game).

You should not need to modify any code outside of the `TankAnt` class. If you find yourself needing to make changes elsewhere, look for a way to write your code for the previous question such that it applies not just to `BodyguardAnt` and `TankAnt` objects, but to `ContainerAnt`'s in general.

Hint: The only methods you need to override from `TankAnt`'s parent class are `__init__` and `action`.

Assignment Project Exam Help

Hint: Like with `FireAnt`, it is possible that damaging a bee will cause it to be removed from its place.

<https://powcoder.com>

After writing code, test your implementation:

```
python3 ok -q 09
```

Add WeChat powcoder

Phase 4: Water and Might

Important submission note: For full credit,

- Submit with all phases complete by **Thursday, December 1**.

You will get an extra credit point for submitting the entire project by **Tuesday, November 29**.

In the final phase, you're going to add one last kick to the game by introducing a new type of place and new ants that are able to occupy this place. One of these ants is the most important ant of them all: the queen of the colony!

Problem 10 (3 pt)

Before writing any code, read the instructions and test your understanding of the problem:

```
python3 ok -q 10 -u
```

Let's add water to the colony! Currently there are only two types of places, the `Hive` and a basic `Place`. To make things more interesting, we're going to create a new type of `Place` called `Water`.

Only an insect that is waterproof can be placed in `Water`. In order to determine whether an `Insect` is waterproof, add a new class attribute to the `Insect` class named `is_waterproof` that is set to `False`. Since bees can fly, set their `is_waterproof` attribute to `True`, overriding the inherited value.

Now, implement the `add_insect` method for `Water`. First, add the insect to the place regardless of whether it is waterproof. Then, if the insect is not waterproof, reduce the insect's health to 0. *Do not repeat code from elsewhere in the program.* Instead, use methods that have already been defined.

After writing code, test your implementation:

```
python3 ok -q 10
```

Once you've finished this problem, play a game that includes water. To access the `wet_layout`, which includes water, add the `--water` option (or `-w` for short) when you start the game.

```
python3 gui.py --water
```

Problem 11 (3 pt)

Before writing any code, read the instructions and test your understanding of the problem:

```
python3 ok -q 11 -u
```

<https://powcoder.com>

Currently there are no ants that can be placed on `Water`. Implement the `ScubaThrower`, which is a subclass of `ThrowerAnt` that is more costly and waterproof, *but otherwise identical to its base class*. A `ScubaThrower` should not lose its health when placed in `Water`.

Class	Food Cost	Initial Health
 ScubaThrower	6	1

Add WeChat powcoder

We have not provided you with a class header. Implement the `ScubaThrower` class from scratch. Give it a class attribute `name` with the value 'Scuba' (so that the graphics work) and remember to set the class attribute `implemented` with the value `True` (so that you can use it in a game).

After writing code, test your implementation:

```
python3 ok -q 11
```

Problem 12 (7 pt)

Before writing any code, read the instructions and test your understanding of the problem:

```
python3 ok -q 12 -u
```

Finally, implement the `QueenAnt`. The queen is a waterproof `ScubaThrower` that inspires her fellow ants through her bravery. In addition to the standard `ScubaThrower` action, the `QueenAnt` doubles the damage of all the ants behind her each time she performs an action. Once an ant's damage has been doubled, it is *not* doubled again for subsequent turns.

Note: The reflected damage of a `FireAnt` should not be doubled, only the extra damage it deals when its health is reduced to 0.

Class	Food Cost	Initial Health
 QueenAnt	7	1

However, with great power comes great responsibility. The `QueenAnt` is governed by three special rules:

Assignment Project Exam Help

1. If the queen ever has its health reduced to 0, the ants lose. You will need to override `Ant.reduce_health` in `QueenAnt` and call `ants_lose()` in that case in order to signal to the simulator that the game is over. (The ants also still lose if any bee reaches the end of a tunnel.)
2. There can be only one queen. After the first queen is constructed, any attempt at constructing a second queen should result in a `DuplicateQueensException`. To keep track of whether a queen has already been created, you can add an instance variable to the `Gamestate` class and use it in the `__init__` of `QueenAnt`.
3. The queen cannot be removed. Attempts to remove the queen should have no effect (but should not cause an error). You will need to override `Ant.remove_from` in `QueenAnt` to enforce this condition.

Hint: You can find each `Place` in a tunnel behind the `QueenAnt` by starting at the ant's `place.exit` and then repeatedly following its `exit`. The `exit` of a `Place` at the end of a tunnel is `None`.

Hint: To avoid doubling an ant's damage twice, mark the ants that have been buffed in some way, in a way that persists across calls to `QueenAnt.action`.

Hint: When buffing the ants' damage, keep in mind that there can be more than one ant in a `Place`, such as if one ant is guarding another.

Hint: Feel free to add new methods to the `QueenAnt` class! Also, make sure to look at the `buff` method in `Ant`.

After writing code, test your implementation:

```
python3 ok -q 12
```

Extra Credit (2 pt)

Before writing any code, read the instructions and test your understanding of the problem:

```
python3 ok -q EC -u
```

Implement two final thrower ants that do zero damage, but instead apply a temporary "status" on the `action` method of a `Bee` instance that they `throw_at`. This "status" lasts for a certain number of turns, after which it ceases to take effect.

We will be implementing two new ants that inherit from `ThrowerAnt`.

- `SlowThrower` throws sticky syrup at a bee, slowing it for 3 turns. When a bee is slowed, it can only move on turns when `gamestate.time` is even, and can do nothing otherwise. If a bee is hit by syrup while it is already slowed, it is slowed for an additional 3 turns.
- `ScaryThrower` intimidates a nearby bee, causing it to back away instead of advancing. (If the bee is already right next to the Hive and cannot go back further, it should not move. To check if a bee is next to the Hive, you might find the `is_hive` instance attribute of `Place`'s useful). Bees remain scared until they have tried to back away twice. Bees cannot try to back away if they are slowed and `gamestate.time` is odd. *Once a bee has been slowed once, it can't be slowed again.*

Assignment Project Exam Help

Class	Food Cost	Initial Health
 SlowThrower	4	1

6

1



Assignment Project Exam Help

ScaryThrower

In order to complete the implementations of these two ants, you will need to set their class attributes appropriately and implement the `slow` and `scare` methods on `Bee`, which apply their respective statuses on a particular bee. You may also have to edit some other methods of `Bee`.

You can run some provided tests, but they are not exhaustive:

```
python3 ok -q EC
```

Add WeChat powcoder

Make sure to test your code! Your code should be able to apply multiple statuses on a target; each new status applies to the current (possibly previously affected) action method of the bee.

Optional Problems

Optional Problem 1

Before writing any code, read the instructions and test your understanding of the problem:

```
python3 ok -q optional1 -u
```

Implement the `NinjaAnt`, which damages all `Bee`s that pass by, but can never be stung.

Class	Food Cost	Initial Health

	5	1
NinjaAnt		

A NinjaAnt does not block the path of a Bee that flies by. To implement this behavior, first modify the `Ant` class to include a new class attribute `blocks_path` that is set to `True`, then override the value of `blocks_path` to `False` in the `NinjaAnt` class.

Second, modify the Bee's method `blocked` to return `False` if either there is no Ant in the Bee's place or if there is an Ant, but its `blocks_path` attribute is `False`. Now Bee's will just fly past NinjaAnt's.

Finally, we want to make the NinjaAnt damage all Bee's that fly past. Implement the `action` method in `NinjaAnt` to reduce the health of all Bee's in the same place as the NinjaAnt by its `damage` attribute. Similar to the `FireAnt`, you must iterate over a potentially changing list of bees.

Hint: Having trouble visualizing the test cases? Try drawing them out on paper! See the example in Game Layout for help.

After writing code, test your implementation:

`python3 ok -q optional`

Assignment Project Exam Help

For a challenge, try to win a game using only HarvesterAnt and NinjaAnt

<https://powcoder.com>

Optional Problem 2

We've been developing this ant for a long time in secret. It's so dangerous that we had to lock it in the super hidden CS88 underground vault, but we finally think it is ready to go out in the field. In this problem, you'll be implementing the final ant — LaserAnt, a ThrowerAnt with a twist.

Note: There are no unlocking tests for this question.

Class	Food Cost	Initial Health
	10	1
LaserAnt		

The `LaserAnt` shoots out a powerful laser, damaging all that dare to stand in its path. Both `Bee`s and `Ant`s, of all types, are at risk of being damaged by `LaserAnt`. When a `LaserAnt` takes its action, it will damage all `Insect`s in its place (excluding itself, but including its container if it has one) and the `Place`s in front of it, excluding the `Hive`.

If that were it, `LaserAnt` would be too powerful for us to contain. The `LaserAnt` has a base damage of 2. But, `LaserAnt`'s laser comes with some quirks. The laser is weakened by 0.25 each place it travels away from `LaserAnt`'s place. Additionally, `LaserAnt` has limited battery. Each time `LaserAnt` actually damages an `Insect` its laser's total damage goes down by 0.0625 (1/16). If `LaserAnt`'s damage becomes negative due to these restrictions, it simply does 0 damage instead.

The exact order in which things are damaged within a turn is unspecified.

In order to complete the implementation of this ultimate ant, read through the `LaserAnt` class, set the class attributes appropriately, and implement the following two functions:

1. `insects_in_front` is an instance method, called by the `action` method, that returns a dictionary where each key is an `Insect` and each corresponding value is the distance (in places) that that `Insect` is away from `LaserAnt`. The dictionary should include all `Insects` on the same place or in front of the `LaserAnt`, excluding `LaserAnt` itself.
2. `calculate_damage` is an instance method that takes in `distance`, the distance that an insect is away from the `LaserAnt` instance. It returns the damage that the `LaserAnt` instance should afflict based on:
 3. The distance away from the `LaserAnt` instance that an `Insect` is.
 4. The number of `Insect`s that this `LaserAnt` has damaged, stored in the `insects_shot` instance attribute.

In addition to implementing the methods above, you may need to modify, add, or use class or instance attributes in the `LaserAnt` class as needed.

<https://powcoder.com>

You can run the provided test, but it is not exhaustive:

```
python3 ok -q optional2
```

Add WeChat powcoder

Make sure to test your code!

Project Submission

At this point, run the entire autograder to see if there are any tests that don't pass:

```
python3 ok
```

You can also check your score on each part of the project, including the extra credit problem:

```
python3 ok --score
```

Once you are satisfied, submit to complete the project.

```
python3 ok --submit
```

If you have a partner, make sure to add them to the project submission on okpy (<https://okpy.org/>).

You are now done with the project! If you haven't yet, you should try playing the game!

```
python3 gui.py [-h] [-d DIFFICULTY] [-w] [--food FOOD]
```

Acknowledgments: Tom Magrino and Eric Tzeng developed this project with John DeNero. Jessica Wan contributed the original artwork. Joy Jeng and Mark Miyashita invented the queen ant. Many others have contributed to the project as well!

The new concept artwork was drawn by Alana Tran, Andrew Huang, Emilee Chen, Jessie Salas, Jingyi Li, Katherine Xu, Meena Vempaty, Michelle Chang, and Ryan Davis.

Assignment Project Exam Help

<https://powcoder.com>

Add WeChat powcoder